

Suprafete propuse :

Lungimea totala a canalelor colectoare 10167m din care:

-DN 200mm-6766m

-DN 250mm-3291m

-DN 315mm-310m

Total camine de viziatre:225 bucati

Total statii de pompare:5 bucati

Lungimea totala a conductelor de refulare:1410m din care:

-DN 63mm-120m

-DN 75mm-500m

-DN 90mm-330m

-DN 125mm-430m

-DN 160mm-15m

Statoe de epurare –amplasata la marginea localitatii cu o capacitate de 407mc/zi